



BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division
SCHEDULE-B

NAME OF THE WORK: Improvements and asphaltting 1st 2nd 3rd and 4th cross (Between 7th main and 8th) Bhuvaneshwari nagara in Bagalagunte ward no. 14 Dasarahalli sub division


Sl. No	Description of work	Unit	Qty	Rate Quoted by Sri K.Jagadish	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	KSRRB 300 - Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3 (P.142/I.19.1 PW, P & ISTD -SR 2016-17)	Cum	310.80	78.2	Rupees Seventy Eight and Twenty Paise Only
2	KSRRB M400-1 For Grading I material construction of granular sub-base by providing coarse graded crushed stone aggregates of Granite/ trap/basalt material spreading in uniform layers with motor grader on prepared surface mixing by a mix in place method with rotawater at OMC, and Compacting with vibratory roller to achieve the desired density, complete as per specifications.by mix in a Place method for coarse Graded Granular Sub Base Material as per 400-2 for grading I material . Page No 155/ Item No. 20.6.1 PWD SR 2016-17	Cum	103.60	1366.63	Rupees One Thousand Three Hundred Sixty Six and Sixty Three Paise Only
3	Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. Specification No. 406 with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.(PWD SR 2016-17, P.No.158, I No.20.18)	Cum	238.28	1590.74	Rupees One Thousand Five Hundred Ninety and Seventy Four Paise Only




Signature of the Contractor


Executive Engineer
Dasarahalli Division
BBMP

4	Providing and applying primer coat with S.S. Bitumen emulsion on prepared surface of granular base such as WBM, WMM including clearing of road surface and spraying primer at the rate of 0.6 kg / sqm using mechanical means complete as per specifications, with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.(PWDSR 2016-17, P.No.161, I No.21.6)	Sqm	1036.00	24.8	Rupees Twenty Four and Eighty Paise Only
5	KSRRB 500-2: Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and/or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. Specification No. KRBS 500-1 MORTH Chapter 5 Page No. 161/ Item No. 21.2/ PWD SR 2016-17	Sqm	2072.00	2.86	Rupees Two and Eighty Six Paise Only
6	KSRRB 500-7: Providing and applying tack coat on the prepared black topped surfaces at 5kg per 10 sqm, heating bitumen in boiler fitted with spray set (Excluding cleaning of road surface) including cost of all Materials, labour, HOM of machineries complete as per specifications. MORTH Chapter 5 Page No. 161/ Item No. 21.7/ PWD SR 2016-17	Sqm	2072.00	10.49	Rupees Ten and Forty Nine Paise Only
7	Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant 40 tonne capacity, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by power roller to achieve the desired density, 50/75mm compacted thickness with 3.3% bitumen but excluding the cost of primer/tack coat with lead incl. cost of all materials, labour, HOM of machineries complete as per specifications with 80/100 grade bitumen using 40/60TPH capacity H.M.P with Mechanical paver Gr II (50/75mm) with 3.3% VG-30 Bitumen as per the directions of Engineer-in-charge of the work (PWDSR 2016-17, P.No.161, I No.21.11.6)	Cum	51.80	4712.14	Rupees Four Thousand Seven Hundred Twelve and Fourteen Paise Only



Signature of the Contractor


Executive Engineer
Dasarahalli Division
BBMP

8	Providing and laying bituminous concrete with hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder and filter transporting the hot mix to work site laying with paver finisher to the required grade, level and alignment. rolling with smooth wheeled vibratory and tandem rollers to achieve the desired compaction as per MORTH Specification clause no 500.9 complete in all respects complete as per specification no 509. using 40/60 TPH Capacity H.M.P With Mechanical paver Gr-II (30 mm to 45 mm) with 6% VG-30 Bitumen (p-164, lt 21.22.6) PWD SR 2016-17	Cum	139.86	6541.3	Rupees Six Thousand Five Hundred Forty One and Thirty Paise Only
9	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Page No. 133 Item No. 17.1 PWD SR 2016-17	Cum	310.80	72.7	Rupees Seventy Two and Seventy Paise Only



Signature of the Contractor



Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer
Dasarahalli Division
BBMP